

To: 1 100164 10-2
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 129-20,326-0000
SW SW NE NE, SEC. 29, T 34 S, R 39
1250 feet from NX section line
1250 feet from E section line
Lease Name Hayward "J" Well # 1
County Morton 101.08
Well Total Depth 3110 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 638

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corp.
Name:
Address P.O. Box 351
Liberal, KS 67905-0351

Abandoned Oil Well _____ Gas Well Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 12:30 p.m. Day: 2 Month: 10 Year: 19 97

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

Work: 4 1/2" at 3110' with 650 sx cement, PBTD 3104', Perfs at 2920-3081' (12 sets)

1st plug pump 25 sx cement and 200 lbs. hulls from 3104-2870',

2nd plug spot 20 sx cement from 738-538',

3rd plug spot 5 sx cement from 40-0'.

10-8-1997
10-13-1997

Plugging Proposal Received by Kevin Strube

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 2 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement with 400 lbs. hulls and displaced to 1300'

2nd plug pumped 110 sx cement from 1300' to surface.. Pressured up to 500 psi.

3rd plug pumped 20 sx cement down 8 5/8" X 4 1/2" annulus and pressured to 500 psi.

Remarks: Used common cement by Sargent & Horton. No casing recovery.

INVOICED
If additional description is necessary, use BACK of this form.)

DATE OCT 22 1997 observe this plugging.

INV. NO. 49235

Signed Gary Winters (TECHNICIAN)