

1 020311

58

API NUMBER 15-189-21,411-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C W/2 NW, SEC. 25, T 34 S, R 39 W/E

3960 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Mahoney "B" Well # 1

Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67901

County Stevens 213.85

Well Total Depth 6580 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1775

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Gabbert/Jones, Inc. License Number 5842

Address English Key Bldg., 333 E. English, #215, Wichita, KS 67202

Company to plug at: Hour: 10 p.m. Day: 7 Month: 5 Year: 19 90

Plugging proposal received from Bill Hawkins

(company name) Gabbert/Jones, Inc. (phone) 316-263-9209

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2900' with 100 sx cement, 2nd plug at 1800' with 50 sx cement,

3rd plug at 700' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:30 a.m. Day: 8 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2900' with 100 sx cement,

2nd plug at 1800' with 50 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 5-16-90

5-11-90

INV. NO. 28145

5-8

Signed Glenn Barlow (TECHNICIAN)

