

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21660-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 19-34S-39W
2310 feet from N Section Line, 330 feet from W Section Line
Lease/Unit Name: LITTELL B Well Number: 3
County: MORTON Total Vertical Depth: 6720 feet

Operator License No.: 4549

Conductor Pipe: Size feet: 218.40

Op Name: ANADARKO PETROLEUM CORPORATION

Surface Casing: Size 8.625 feet: 1740

Address: 17001 NORTHCHASE DRIVE
HOUSTON, TX 77060

Production: Size feet:

Liner: Size feet:

Well Type: DH

UIC Docket No:

Date/Time to Plug: 02/03/2002 2:30 PM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Revd. from: KENNY PARKS

Company: ANADARKO

Phone: (852) 601-3130

Proposed Plugging Method: 1ST PLUG AT 3050' WITH 100 SX CMT. 2ND PLUG AT 1740' WITH 50 SX CMT. 3RD PLUG AT 660' WITH 25 SX CMT. 4TH PLUG AT 40-0' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 02/03/2002 5:30 PM

KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG AT 3050' WITH 100 SX CMT. 2ND PLUG AT 1740' WITH 50 SX CMT. 3RD PLUG AT 660' WITH 25 SX CMT. 4TH PLUG AT 40-0' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
MAR - 1 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON.

Plugged through: DP

District: 01

Signed

Steve Durrant

(TECHNICIAN)

FEB 26 2002

INVOICED

DATE 3-04-02

INV. NO. 2002061434