

1 020249

8-8

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 189-21,366-0000
E/2 NE, SEC. 10, T 34 S, R 39 W/E
3890 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Stainbrook "C" Well # 1H

Operator: Anadarko Petroleum Corporation
Name &

County Stevens 53.76

Address P.O. Box 351

Well Total Depth 1654 feet

Liberal, KS 67905-0351

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 559

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Gabbert-Jones, Inc. License Number 5842

Address Wichita, KS 67202

Company to plug at: Hour: 8 a.m. Day: 8 Month: 8 Year: 19 89

Plugging proposal received from Jim Barlow

(company name) Anadarko Petroleum Corp. (phone) 316-624-6253

were: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 1400' with 50 sx cement,
2nd plug at 575' with 50 sx cement,
3rd plug at 40-0' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
8-11-1989
AUG 11 1989
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 10:30 a.m. Day: 8 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1400' with 50 sx cement,
2nd plug at 575' with 50 sx cement,
3rd plug at 40-0' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Lost circulation at 1200'.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Glenn R. Barlow (TECHNICIAN)

DATE 8-16-89

INV. NO. 25614 8-8 OCT 04 1989 NOV 06 1989

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL
HUGOTON INFILL

Starting Date 07 / 27 / 89
month day year

API Number 15-189-21,366

OPERATOR: License # 4549
Name Anadarko Petroleum Corporation
Address P.O. Box 351
City State Zip Liberal, Kansas 67905-0351
Contact Person Jim Barlow
Phone (316) 624-6253

E/2 NE Sec. 10 Twp. 34 S. Rg. 39 W
3890 Ft. from South Line of Section
660 Ft. from East Line of Section

CONTRACTOR: License # 5842
Name Gabbert-Jones, Inc.
City State Wichita, Kansas 67202
Well Drilled as: New Recompletion OWWO
Projected Total Depth 2970 feet
Formation Hugoton

NOTE: Attach acreage attribution plat locating both Chase (Hugoton) wells
Total number of acres attributed to unit 640

If OWWO or Recompletion: add well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Nearest producing well from
same common source of supply 2789 feet
Nearest lease or unit boundary line 1250 feet
County Stevens
Lease Name STAINBROOK "C" Well # 1H
Ground surface elevation 3255 feet MSL
Depth to bottom of fresh water 518-520'
Depth to bottom of usable water 538-540'
Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 560'

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 7/29/89 Signature of Operator or Agent Jim Barlow Title Drilling Supervisor

For KCC Use:

Conductor Pipe Required 20.5 feet; Minimum Surface Pipe Required 560' feet per Alt. X
This Authorization Expires 1-29-90 Approved By DPW 7-24-89

EFFECTIVE DATE: 7-29-89

10 86

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1989

CONSERVATION DIVISION
Wichita, Kansas

PUSHER	_____
TD	_____
FORMATION	_____
SURFACE PIPE @	_____
ANHYDRITE	_____
ELEVATION	_____
STARTING TIME & DATE	_____
COMPLETION TIME & DATE	_____
1st PLUG @	_____ FT. W/ _____ SX
2nd PLUG @	_____ FT. W/ _____ SX
3rd PLUG @	_____ FT. W/ _____ SX
4th PLUG @	_____ FT. W/ _____ SX
RAI HOLE CIRCULATED W/	_____ SX
MOUSE HOLE CIRCULATED W/	_____ SX
WATER WELL PLUGGED W/	_____ SX
CEMENT COMPANY	_____
TECHNICIAN	_____
TYPE OF CEMENT	_____

SPUD
8-4-89
560'-8⁵/₈"

Drill pits must be closed within 365 days of spud date. Extensions may be granted upon application to the Commission.

I hereby certify that the above statements are true and correct to the best of my