

1090954

TO: STATE CORPORATION COMMISSION 160'N 170'E NW SW SW SEC. 9, T 34 S, R 39 W
API NUMBER 15-129-21,569-0000

10-8

CONSERVATION DIVISION - PLUGGING SECTION 1150 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 500 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HJV HAYWARD "O" WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY MORTON

OPERATOR LICENSE # 4549 WELL TOTAL DEPTH 6867 223.18 FEET

OPERATOR: ANADARKO PETROLEUM PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 351 SURFACE CASING: SIZE 8 5/8 " FEET 1780'

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR NORSEMAN DRILLING LICENSE NUMBER 3779

ADDRESS 200 E FIRST ST, STE., 307 WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 7:00 AM DAY: 08 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM STEVE

(COMPANY NAME) NORSEMAN DRILLING (PHONE) 316-265-9408

WERE:

1ST PLUG AT 3160' WITH 100 SX CEMENT, 2ND PLUG AT 1790' WITH 50 SX CEMENT,

3RD PLUG AT 600' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

 PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 10:05 AM DAY: 08 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPES

1ST PLUG AT 3160' WITH 100 SX CEMENT, 2ND PLUG AT 1790' WITH 50 SX CEMENT,

3RD PLUG AT 600' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

866/71-01
OCT 11 10 55 AM '98
STATE CORPORATION COMMISSION

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED [Signature]
(TECHNICIAN) FORM CP-2/3

10-15-98
60111

[Signature]