

1090152

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-20,694-0000

C E/2 SW/4, SEC. 8, T 34 S, R 39 W/E

1420 feet from N/S section line

1980 feet from W/E section line

F. A. Thompson

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Lease Name "B" Unit Well # 1

Operator: Mobil Oil Corporation

County Morton

Name & Address P. O. Box 5444

Well Total Depth 6659 216.42 feet

Denver, CO 80218

Conductor Pipe: Size _____ feet

Surface Casing: Size 9 5/8 feet 1785

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Unit Drilling & Expl. Company License Number 9137

Address 1101 Petroleum Club Building, Tulsa, OK 74119

Company to plug at: Hour: 2:00 am Day: 11 Month: April Year: 19 84

Plugging proposal received from Rick Henderson

(company name) Mobil Oil Corporation (phone) 303-298-2046

were: Logging tool not radio active - lost fishing tool in the hole - stuck mill stub with drill collar at 4249'

Fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2940' in Council Grove with 100 sx Class H Neat cement

2nd plug at 1890' with 100 sx Class H Neat cement with 2% CaCl added - waited on cement and tagged plug top at 1677'

3rd plug at 870' with 50 sx Class H Neat cement

4th plug at 40' with 20 _____ Plugging Proposal Received by R. Carlisle _____
sx Class H Neat cement, Circulate rathole with 15 sx Class H Neat (TECHNICIAN) through 1 joint
of drill pipe. Circulate mousehole with 20 sx cement. Water well plugged by Carlisle.

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:00 pm Day: 11 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2940' in Council Grove with 100 sx Class H Neat cement

2nd plug at 1890' with 100 sx Class H Neat cement with 2% CaCl added - waited on cement and tagged plug top at 1677', 3rd plug at 870' with 50 sx Class H Neat cement, 4th plug

at 40' with 20 sx Class H Neat cement, circulate rathole with 15 sx Class H Neat cement

through 1 joint of drill pipe. Circulate mousehole with 20 sx cement. Water well

plugged by Carlisle Water Well Service

Remarks: Cementing by Dowell Ticket No. 03-12-6290

(if additional description is necessary, use BACK of this form.)

INVOICED (XXXX) observe this plugging.

DATE 4-17-84

INV. NO. 1161 4-11 APR 20 1984

Signed R. Carlisle (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION APR 16 1984 CONSERVATION DIVISION Wichita, Kansas