

1 020376

4-29

414

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,971-0000

C W/2 NE, SEC. 4, T 34 S, R 39 W/E

3960 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Dole "A" Well # 1

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-3051

County Morton 224.25

Well Total Depth 6900 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1779

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 3:30 p.m. Day: 26 Month: 4 Year: 19 91

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 6345' w/175 sx cement, PBTD 6170', Perfs at 5980-6000'

1st plug pump 2 sx hulls and 25 sx cement at perfs, displace with mud,

2nd plug pump 35 sx cement at 2700',

3rd plug pump 50 sx cement at 1800',

4th plug pump 30 sx cement at 800', 5th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5 p.m. Day: 29 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement at perfs, displaced hole with mud,

2nd plug pumped 35 sx cement at 2700',

3rd plug pumped 50 sx cement at 1800',

4th plug pumped 30 sx cement at 800',

5th plug circulated 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 3816' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (if no documents) observe this plugging.

DATE 5-9-91

INV. NO. 31777

Signed Glenn Barlow RECEIVED STATE CORPORATION COMMISSION (TECHNICIAN)

MAY 06 1991
FORM CP-2/3
CONSERVATION DIVISION-84
Wichita, Kansas