

To: 1 070012 7-23
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 129-21,520 - 0000
C NE SW, SEC. 4, T 34 S, R 39 W/EX
1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5363

Lease Name Armstrong Well / 1-4

Operator: BEREXCO, Inc.
Name & Address 100 N. Broadway, Ste. 970
Wichita, KS 67202

County Morton 209.33
Well Total Depth 6441 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1811

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Sweetman Drilling, Inc. License Number 5658

Address 3017 N. Cypress Dr., Wichita, KS 67226-4003

Company to plug at: Hour: 5 a.m. Day: 23 Month: 7 Year: 1997

Plugging proposal received from Eugene Saloga

(company name) Sweetman Drilling, Inc. (phone) 316-634-6151

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1728-1804'
1st plug at 3200' with 100 sx cement, 2nd plug at 1830' with 50' sx cement,
3rd plug at 560' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Scott Alberg (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:40 a.m. Day: 23 Month: 7 Year: 1997

ACTUAL PLUGGING REPORT 1st plug at 3200' with 100 sx cement,
2nd plug at 1830' with 50 sx cement,
3rd plug at 560' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
(if applicable) observe this plugging.

DATE 7-30-97

Signed [Signature] (TECHNICIAN)

INV. NO. 48687