

15-129-00339-0000

1 110099

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 - Drill Completion Date 6/19/30

C SW, SEC. 4, T 34 S, R 39 W/EX
1320 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Lease Name Armstrong #2 Unit 2 Well # 2

Operator: Mobil Oil Corporation
Name & Address: P.O. Box 5444
Denver, CO 80217

County: Morton 90.51

Well Total Depth 2785 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 12 1/2 feet 600

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mobil Oil Corporation License Number 5208

Address P.O. Box 5444, Denver, CO 80217

Company to plug at: Hour: 9:30 a.m. Day: 2 Month: 3 Year: 19 88

Plugging proposal received from Monty Deitz

(company name) Mobil Oil Corporation (phone) 303-298-2696

were: 8 5/8" at 2550' 7" slotted liner 2531-2785' Perfs at 2595-2675, 2685-2740', 2745-85'

1st plug pump 70 sx cement at 1350', 2nd plug shoot at 650' and squeeze with cement,

filling hole to '0'.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 11:30 a.m. Day: 3 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 70 sx cement at 1350',

2nd plug shot at 651' and squeezed with 464 sx cement,

3rd plug finished filling with cement on 3/3/88. with 25 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR - 9 1988
3-9-1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: No casing recovery. Used 50/50 Pozmix by Halliburton.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

Signed James R. Papp
(TECHNICIAN)

DATE 3-10-88

INV. NO. 20072