

1100264 , J
TO:
STATE CORPORATION COMMISSION 12-1

API NUMBER 15-189-20,245-0000
SE SE SW NW SEC. 3, T 34 S, R 39 W

CONSERVATION DIVISION - PLUGGING SECTION 2540 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1250 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME NIX "B" WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY STEVENS 97.01

OPERATOR LICENSE # 4549 WELL TOTAL DEPTH 2985 FEET

OPERATOR: ANADARKO PETROLEUM CORP PRODUCTION CSG: SIZE 5 1/2" @ 2985' WITH 650 SX

NAME AND PO BOX 351 SURFACE CASING: SIZE 8 5/8" @ 492' WITH 450 SX

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 01 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING (PHONE) 405-854-6515

WERE: PERFS AT 2930-2979

PUMP 2 SX HULLS & 35 SX CEMENT. DISPLACE TO 2880' WITH 9 PPG MUD. PLACE 35 SX CEMENT

FROM 392-592'. PLACE 15 SX CEMENT FROM 54-4'. FILL ANNULAS BETWEEN 8% CASING AND 5%

CASING WITH CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 01 MONTH: 1 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG PUMP 200# HULLS WITH 25 SX CEMENT TO 2960' PUT GEL SPACER TO 1700'. 2ND PLUG

SPOT 25 SX PLUG INSIDE 5% AT 1700'. RUN GEL SPACER TO 520'. 3RD PLUG SPOT 25 SX PLUG AT

520' INSIDE 5%. RUN GEL SPACER TO 40'. 4TH PLUG SPOT 10 SX PLUG AT 42' TO 0'.

CEMENT HELD AT SURFACE.

REMARKS: USED NEAT CEMENT BY SARGENTS. NO CASING RECOVERED CEMENT TO SURFACE NO STRETCH

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED

Gary Winters
(TECHNICIAN)

FORM CP-2/3

DEC 15 1998

60428

RAY