

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-129-21,153-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549 8/94  
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE      CYR "A" WELL# 1 SEC. 30 T. 34S R. 41 (XXXX West)

SE - SE - NE - NW SPOT LOCATION/QQQQ COUNTY MORTON

1250 FEET (in exact footage) FROM X (N) (circle one) LINE OF SECTION (NOT Lease Line)

2700 FEET (in exact footage) FROM (E)X (circle one) LINE OF SECTION (NOT Lease Line)

**Check One:** OIL WELL      GAS WELL X D&A      SWD/ENHR WELL      DOCKET#     

CONDUCTOR CASING SIZE      SET AT      CEMENTED WITH      SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1414' CEMENTED WITH 700 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 2244' CEMENTED WITH 75 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2130 - 2146

ELEVATION 3458' -- T.D. 2245' PBTD 2244' ANHYDRITE DEPTH       
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR      CASING LEAK      JUNK IN HOLE     

PROPOSED METHOD OF PLUGGING MIRU CSG PULLERS. TIH W/ 1-1/4" TBG. CIRCULATE HOLE W/9 PPG (MINIMUM) DRILLING MUD. PUMP 2 SX HULLS & 20 SX CLASS H AT 2146-1989'. PULL FREE POINT IN 5-1/2" CSG AND CUT OFF. PULL CSG 50'. PMP 23 SX CLASS H AT CUTOFF DEPTH. PULL 5-1/2" CSG TO 450'. PMP 35 SX CLASS H CMT FROM 450-350'. PULL 5-1/2" CSG TO 53'. PMP 18 SX CLASS H CMT FROM 53-3'. REMOVE 5-1/2" CSG FROM WELLBORE. CUT OFF 8-5/8" CSG 3' BELOW GROUND LEVEL AND CAP. RESTORE LOCATION AND CLEAN UP.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?      IS ACO-1 FILED? YES

If not explain why?     

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MARVIN JOHNSON PHONE# (316) 697-2188

ADDRESS P.O. BOX 351 City/State ELKHART, KANSAS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151 1/95  
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8-23-94 AUTHORIZED OPERATOR/AGENT: [Signature]  
J. L. ASHTON (signature) DIV. PROD. MGR.



## Kansas Corporation Commission

Joan Finney, Governor    Susan M. Seltsam, Chair    F.S. Jack Alexander, Commissioner    Rachel C. Lipman, Commissioner  
Judith McConnell, Executive Director    Brian Moline, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

August 31, 1994

Anadarko Petroleum Corporation  
P O Box 351  
Liberal KS 67905-0351

Cyr "A" #1  
API 15-129-21,153  
1250 FNL 2700 FEL  
Sec. 30-34S-41W  
Morton County

Dear Marvin Johnson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City KS 67801  
(316) 225-6760

William R. Bryson, Director Conservation Division  
KCC, Conservation Division, Wichita State Office Building  
130 S. Market, Room 2078, Wichita, Kansas 67202 (316) 337-6200