

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-093-20812-00-00
Spot: SENWNESE Sec/Twnshp/Rge: 20-25S-36W
2300 feet from S Section Line, 690 feet from E Section Line
Lease Name: LEE Well #: 20-1
County: KEARNY Total Vertical Depth: 5030 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5030	0	WITH 730 SX CMT
SURF	8.625	629		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/18/2015 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOSE Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/20/2015 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

3/18/15: ATTEMPT TO SET CIBP OVER PERFS. COULD NOT GET PAST 3300'. RUN 4 7/8" BIT & GOT TO 3418' & COULD NOT GET DEEPER. GETTING BACK METAL IN RETURNS. RAN BOND LOG. SHOWS A STAGE TOOL OR PERFS @ 1814' TO 1817'. BOTTOM OF CMT @ 1830' & TOC @ 320'. 3/19/15: RUN TBG TO 3305' & SPOT 75 CLASS A COMMON CEMENT WITH 3% CC & 100# HULLS. FULL CIRCULATION. PUMP 25 SX CMT CLASS A CEMENT AT 1843'. HAD CIRCULATION. PULL TO 840'. PUMP 100 SX CMT & LOST CIRCULATION. CONTINUE PUMPING ANOTHER 25 SX CMT WITH NO RETURNS. SDON. 3/20/15: TAG TOC WITH TBG @ 1060'. FILL CASING WITH CMT FROM 1030' TO 0' WITH 100 SX CMT. PUMP 25 SX CMT DOWN THE ANNULUS TO 200#.

Perfs:

Top	Bot	Thru	Comments
4818	4969		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED CLASS A & 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01


Signed



(TECHNICIAN)

4/15/15 CKM

RECEIVED
APR - 3 2015
KCC DODGE CITY



Received
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 13 2015

CONSERVATION DIVISION
WICHITA, KS