

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-189-22193-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 32-33S-38W  
2330 feet from N Section Line, 1011 feet from W Section Line  
Lease Name: GREGORY C Well #: 3  
County: STEVENS Total Vertical Depth: 6400 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6087		WITH 2 SX CMT
CIBP		6187		
PROD	5.5	6296	1786	WITH 150 SX CMT
SURF	8.625	1732		WITH 435 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/25/2015 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 6087' WITH 2 SX CMT. 1ST PLUG AT 1786' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 560' WITH 50 SX CMT. 3RD PLUG AT 44' WITH 20 SX CMT. CMT CIRCULATED.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: NONE  
Date/Time Plugging Completed: 03/25/2015 3:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 6087' WITH 2 SX CMT. 1ST PLUG AT 1786' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 560' WITH 50 SX CMT. 3RD PLUG AT 44' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6151	6208		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

4/15/15 CKM

RECEIVED  
APR - 8 2015  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 13 2015  
CONSERVATION DIVISION  
WICHITA, KS