

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-03229-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 16-24S-18E
4460 feet from S Section Line, 1125 feet from E Section Line
Lease Name: CLINE Well #: C9
County: ALLEN Total Vertical Depth: 885 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	847		110 SX
SURF	8.25	18		3 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2015 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: RICK RICE Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: COMPANY SERVICE UNIT RIH 1" TBG TO BTM. SERVICE UNIT HOOK ON TO 1" TBG PUMPED CMT TO SURFACE COMPANY SERVICE UNIT PULLED TBG OUT SERVICE UNIT TOP WELL OFF. WILL COME BACK LATER CUT CSG OFF "BELOW PLOW DEPTH"

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 01/23/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2" casing to TD. Ran 1" pipe down the backside of the 2" casing inside the 8" surface casing to approximately 200'. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled the 1" pipe. Pumped and circulated cement through the 1" pipe that was on the backside of the 2" casing inside the 8" casing from approximately 200' to surface. Pulled the 1" pipe. A total of 80 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
847	885		
RECEIVED KCC DIST # 3 APR 07 2015 CHANUTE, KS RD			

Remarks:

Plugged through:

District: 03

Signed [Signature] 4/15/15
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 09 2015
CONSERVATION DIVISION
WICHITA, KS