

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-27188-00-00  
Spot: E2NENW Sec/Twnshp/Rge: 24-25S-19E  
4620 feet from S Section Line, 3260 feet from E Section Line  
Lease Name: WOLFE Well #: 44  
County: ALLEN Total Vertical Depth: 889 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD   | 2.875 | 887        |             | 110 SX  |
| SURF   | 6.25  | 20         |             | 6 SX    |

Well Type: EOR UIC Docket No: E10334.90 Date/Time to Plug: 01/22/2015 12:00 AM  
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC  
Proposal Rcvd. from: RICK RICE Company: Phone: (620) 365-3111

Proposed Plugging Method: COMPANY SERVICE UNIT RIH 1" TBG TO TD FILL TO SURFACE W/CEMENT - PULL 1" OUT TOP WELL OFF.

Plugging Proposal Received By: RYAN DULING WitnessType: NONE  
Date/Time Plugging Completed: 01/22/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe inside the 2.875" casing to T.D. Pumped and circulated cement through the 1" pipe inside the 2.875" casing from TD to surface. Pulled the 1" pipe out of the well and topped the well off with cement. A total of 35 sacks of portland cement was reported used to plug this well.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 845 | 868 |      |          |

RECEIVED  
KCC DIST # 3  
APR 07 2015  
CHANUTE, KS  
RD

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]  
(TECHNICIAN)

4/15/15 CKM

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 09 2015

CONSERVATION DIVISION  
WICHITA, KS

CC:UIC