

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-27980-00-00
Spot: NENWNW Sec/Twnshp/Rge: 24-25S-19E
5070 feet from S Section Line, 4180 feet from E Section Line
Lease Name: WOLFE Well #: RW 25
County: ALLEN Total Vertical Depth: 895 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	895		90 SX
SURF	6.25	20		0 SX

Well Type: EOR UIC Docket No: E10334.80 Date/Time to Plug: 01/22/2015 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Revd. from: RICK RICE Company: Phone: (620) 365-3111

Proposed Plugging Method: COMPANY SERVICE UNIT RIH 1" TBG TO TD. SERVICE COMPANY FILL TO SURFACE W/CEMENT
COMPANY SERVICE UNIT PULLED 1" OUT TOPPED WELL OFF. WILL GO BACK AT LATER DATE AND CUT SURFACE OFF BELOW PLOW DEPTH.

Plugging Proposal Received By: RYAN DULING WitnessType: NONE
Date/Time Plugging Completed: 01/22/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe inside the 2.875" casing to T.D. Pumped and circulated cement through the 1" pipe inside the 2.875" casing from TD to surface. Pulled the 1" pipe out of the well and topped the well off with cement. A total of 35 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
857	869		

RECEIVED
RECEIPT # 3
KCC DIST # 3
APR 07 2015
CHANUTE, KS
CHANUTE, KS
RD

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

APR 09 2015
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

CC:UIC