

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-22294-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 11-18S-7W  
4290 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: JANSSEN C Well #: 3  
County: RICE Total Vertical Depth: 3190 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 522 N. MAIN ST PO BOX 560  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2960		
PROD	4.5	3147		115 SX
SURF	8.625	216		130 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/27/2015 12:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/27/2015 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, TAG CIBP. PERFORATE @950', 600', AND 265'. CAP CIBP WITH 2 SX'S CEMENT. RUN TUBING TO 950' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CC. PULL TUBING UP TO 600'. LET SET FOR 1 HR., THEN TAGGED CEMENT WITH SWAB BAR @900'. PUMP 35 SX'S COMMON CEMENT @ 600', PULL TUBING TO 265' AND CIRCUALTE 60-40 POZ, 4% GEL TO SURFACE. PULL TUBING OUT AND TOP OFF. USED APPROX. 190 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3062	3065	CSG	
2997	3000	CSG	

Remarks: WELL HAD FAILED MIT FOR TA ON 2-25-2015. LOG TECH OF KS PERF #8447. COPELAND CEMENT #C-41042.

Plugged through: TBG

*4/15/15 CKM*

District: 02

Signed Virgil Clothier  
(TECHNICIAN)  
KCC WICHITA

APR 14 2015

RECEIVED