

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24451-00-00
Spot: N2NWNWNE Sec/Twnshp/Rge: 29-16S-23W
158 feet from N Section Line, 2293 feet from E Section Line
Lease Name: DIETTERICH-MISHLER Well #: 1-29
County: NESS Total Vertical Depth: 4600 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4430		WITH 2 SX CMT
PC		1852		WITH 170 SX CMT
PROD	7.875	4598	0	WITH 150 SX CMT
SURF	8.625	220		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/31/2015 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA Phone: (620) 617-3357

Proposed Plugging Method: SET CIBP @ 4430' WITH 2 SX CMT. RUN TBG TO 1870' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: ROBERT DICKERSON WitnessType: NONE
Date/Time Plugging Completed: 03/31/2015 1:00 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 4430' WITH 2 SX CMT. PUMP CMT FROM 2000' TO SURFACE WITH 190 SX CMT. TIE ON BACKSIDE & SQUEEZE 10 SX CMT IN.

Perfs:

Top	Bot	Thru	Comments
4486	4496		
4481	4482		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

4.15.15 CKM

District: 01

Signed Robert Dickerson

(TECHNICIAN)

RECEIVED
APR - 3 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 13 2015

CONSERVATION DIVISION
WICHITA, KS