

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21137-00-00
Spot: NWSENE Sec/Twnshp/Rge: 27-27S-5E
3752 feet from S Section Line, 1001 feet from E Section Line
Lease Name: PARKS Well #: 2-A
County: BUTLER Total Vertical Depth: 2800 feet

Operator License No.: 32843
Op Name: LED ENTERPRISES LLC
Address: 801 FREDRICK DR.
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2798		75 SX
SURF	8.625	202		139 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2015 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: DENNIS BUTLER Company: LED ENTERPRISES Phone: (316) 323-4654

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 03/18/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2616', DUMP BAILED 3 SXS CEMENT ON TOP OF SAND. RIH ON WIRELINE CUT CASING @288', LAYED DOWN 8 JOINTS 5 1/2" CASING (288'). RIH W/ TBG @ 260', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCUALTION, MIXED & PUMPED 98 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. CONSOLIDATED CEMENT TICKET #48362.

Perfs:

Remarks: COMPLIANCE 10/ YR RULE

Plugged through: TBG

4/15/15 CKM

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

KCC WICHITA

APR 14 2015

RECEIVED