

TO:
STATE CORPORATION COMMISSION.
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21224-00-00
Spot: SWSESW Sec/Twnshp/Rge: 27-27S-5E
420 feet from S Section Line, 3625 feet from E Section Line
Lease Name: BIRD Well #: 4
County: BUTLER Total Vertical Depth: 2810 feet

Operator License No.: 32843
Op Name: LED ENTERPRISES LLC
Address: 801 FREDRICK DR.
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2809	553	90 SX
SURF	8.625	200		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2015 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: DENNIS BUTLER Company: LED ENTERPRISES Phone: (316) 323-4654

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 03/18/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2660', DUMP BAILED 3 SXS CEMENT ON TOP OF SAND. RIH ON WIRELINE CUT CASING @ 553', LAYED DOWN 14 JOINTS 5 1/2" CASING (553'). RIH W/4 1/2" DUMP BAILOR, BAILED FLUIDS @ 250', CMC DUMPED 5.5 YARDS (117 SXS) SLURRY MIX LESS 10% SAND TO SURFACE CEMENT CIRCULATED. CMC CEMENT TICKET #400040167.

Perfs:

Top	Bot	Thru	Comments
2719	2728		CSG

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

4.15.15 CKM

District: 02

Signed Duane Krueger
(TECHNICIAN)

KCC WICHITA

APR 14 2015

RECEIVED