

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23000-00-00
Spot: SENENE Sec/Twnshp/Rge: 27-27S-5E
4045 feet from S Section Line, 658 feet from E Section Line
Lease Name: PARKS A Well #: 6
County: BUTLER Total Vertical Depth: 2818 feet

Operator License No.: 32843
Op Name: LED ENTERPRISES LLC
Address: 801 FREDRICK DR.
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2816	751	100 SX
SURF	8.625	207		115 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2015 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Revd. from: DENNIS BUTLER Company: LED ENTERPRISES Phone: (316) 323-4654

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 03/23/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2688', DUMP BAILED 3 SXS CEMENT ON TOP OF SAND. RIH ON WIRELINE CUT CASING @ 751', LAYED DOWN 20 JOINTS 5 1/2" CASING (751'). RIH W/ 4 1/2" DUMP BAILOR, BAILED WELL @ 270', CMC DUMPED 5 1/2 YDS (117 SXS) SLURRY MIX LESS 10% SAND TO SURFACE. CEMENT CIRCUALTED. CMC CEMENT TICKET #400040197.

Perfs:

Top	Bot	Thru	Comments
2746	2756		CSG

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

4/15/15 CRM

KCC WICHITA

APR 14 2015

RECEIVED