

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21844-00-00
Spot: E2E2 Sec/Twnshp/Rge: 27-26S-32W
2654 feet from N Section Line, 708 feet from E Section Line
Lease Name: JLM FARMS Well #: 1-827
County: FINNEY Total Vertical Depth: 5220 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL RD STE 1200
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4898		WITH 5 SX CMT
PC		2097		
PROD	4.5	5225	1748	WITH 120 SX CMT
SURF	8.625	1714		WITH 725 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2015 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: ALAN Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4900' WITH 2 SX CMT. PLUG AT 1870' WITH 10 SX GEL & 50 SX CMT. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/25/2015 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4898' WITH 5 SX CMT. 1ST PLUG AT 1767' WITH 75 SX CMT. 2ND PLUG AT 995' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4954	4962		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

RECEIVED
APR - 8 2015
KCC DODGE CITY

Signed

Ken Jehlik
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

APR 13 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

4/15/15 ckm