

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-20551-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 33-34S-43W
363 feet from S Section Line, 2267 feet from E Section Line
Lease Name: LENCUT Well #: 5
County: MORTON Total Vertical Depth: 3537 feet

Operator License No.: 33373
Op Name: NAIRN, ROBERT
Address: 1120 MUNCY AVE
ELKHART, KS 67950

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1263	0	WITH 350 SX CMT
SURF	8.625	402		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/02/2015 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CMT BOTTOM TO 1130'. CEMENT 460' TO SURFACE. GEL & MUD SPACER

Plugging Proposal Received By: SCOTT ALBERG WitnessType: PARTIAL
Date/Time Plugging Completed: 04/02/2015 11:00 AM KCC Agent: WADE KLAUS

Actual Plugging Report:

PUMP 25 SX CMT & 120# HULLS TO BOTTOM. TAGGED CMT AT 1048'. FLUID LEVEL AT 460'. PUMP 55 SX CMT AT 460' TO SURFACE. HELD PRESSURE AT 400#.

Perfs:

Top	Bot	Thru	Comments
1270	1278		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

4/15/15 CKM

District: 01

Signed [Signature]
(TECHNICIAN) [Signature]

RECEIVED
APR - 6 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
APR 13 2015
CONSERVATION DIVISION
WICHITA, KS