

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-025-21583-00-00  
Spot: S2N2NWNW Sec/Twnshp/Rge: 10-31S-24W  
335 feet from N Section Line, 660 feet from W Section Line  
Lease Name: PRATHER Well #: 2-10  
County: CLARK Total Vertical Depth: 5750 feet

Operator License No.: 32211  
Op Name: O'BRIEN ENERGY RESOURCES CORP.  
Address: 18 CONGRESS ST, STE 207  
PORTSMOUTH, NH 03801

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	726		WITH 260 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/03/2015 12:00 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: ROGER PEARSON Company: O'BRIEN ENERGY RESOURCES Phone: (603) 427-2099

Proposed Plugging Method: 1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE  
Date/Time Plugging Completed: 03/03/2015 12:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: DP

4/15/15 CCM

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
APR - 9 2015  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION  
APR 13 2015  
CONSERVATION DIVISION  
WICHITA, KS  
Form CP-2/3