

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21295-00-00
Spot: SESE Sec/Twnshp/Rge: 33-23S-15W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: HAS (SHOOP) Well #: 1
County: PAWNEE Total Vertical Depth: 4118 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3930		WITH 2 SX CMT
PROD	4.5	4112		150 SX
SURF	8.625	303		175 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/25/2015 11:30 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: CIBP @ 3930' & 2 SX CMT. PLUG AT 980' WITH 15 SX GEL & 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/27/2015 9:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 3930' WITH 2 SX CMT. 1ST PLUG AT 1008' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 378' WITH 50 SX CMT. 3RD PLUG AT 80' WITH 20 SX CMT. CMT CIRCULATED BUT FELL. TOPPED OFF WITH THE LAST 15 SX CMT ON BULK TRUCK. CMT CAME WITHIN 5' OF SURFACE BUT CONTINUED TO SLOWLY DROP. 3/27/15: TOC WAS 184' FROM SURFACE. TOPPED OFF WITH SACK CEMENT.

Perfs:

Top	Bot	Thru	Comments
3989	4074		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

4.15.15 CKM

District: 01

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

APR 13 2015

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
APR - 3 2015
KCC DODGE CITY

Form CP-2/3