

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-20448-00-01
Spot: SESESE Sec/Twnshp/Rge: 7-27S-13W
335 feet from S Section Line, 376 feet from E Section Line
Lease Name: WATSON Well #: 1
County: PRATT Total Vertical Depth: 4618 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4357		WITH 2 SX CMT
PROD	4.5	4450	0	WITH 200 SX CMT
SURF	10.75	280		WITH 275 SX CMT

Well Type: SWD UIC Docket No: D19334.0 Date/Time to Plug: 04/09/2015 1:30 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: KENNETH C GATES Company: PRATT WELL SERVICE, INC. Phone: (620) 672-9571

Proposed Plugging Method: SET CIBP @ 4400' WITH 2 SX CMT. PERFORATE AT 950'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/09/2015 3:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SAND BACK TO 4363'. SET CIBP @ 4357' & DUMP 2 SX CMT ON TOP WITH BAILER. RAN BOND LOG. TOC @ 690'. ANHYDRITE AT 900'. PERFORATE AT 680' WITH 2 SHT/FT. RUN 2 3/8" TBG TO 662'. ESTABLISH CIRCULATION BETWEEN 4 1/2" X 10 3/4" ANNULUS. SHUT IN. FILL 4 1/2" CASING TO SURFACE WITH CMT. PUMP UP 4 1/2" X 10 3/4", CMT TO SURFACE. PULL TBG. TOP OFF 4 1/2" WITH CMT. USED A TOTAL OF 300 SX CMT. (4 1/2" TOOK 55 SX, 4 1/2" X 10 3/4" TOOK 245 SX CMT.)

Perfs:

Top	Bot	Thru	Comments
4450	4618	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
APR 10 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

APR 13 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

cc:uic