

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24314-00-00
Spot: E2SWSW Sec/Twnshp/Rge: 7-19S-23W
630 feet from S Section Line, 1050 feet from W Section Line
Lease Name: STUM Well #: 1
County: NESS Total Vertical Depth: 4418 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1485		
PROD	5.5	4406	0	WITH 165 SX CMT
SURF	8.625	238		WITH 170 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/25/2015 2:30 PM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: MORRIS SMITH Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP GEL THEN 35 SX CMT & 150# HULLS. PULL TBG TO 1500' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/25/2015 4:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4336' & PUMP 35 SX CMT & 150# HULLS. PULL TBG TO 1500' & PUMPED 150 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
4406	4418	OH	
4283	4288		


Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

4/15/15 CKM

District: 01

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

APR 13 2015

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
APR - 3 2015
KCC DODGE CITY



Form CR-2/3

