

4-27
4-050191

TO: API number: 15-063-20,557-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW NE /4 SEC. 28, 14 S, 29 W
3080 feet from S section line
2200 feet from E section line

Operator license# 5886 Lease Lundgren well# 1

Operator: Chief Drilling Inc. County Gove

Address: 120 S. Market #300 Well total depth 4370 feet ^{142.02}
Wichita, Kansas 67202 Conductor Pipe: _____ inch @ _____ feet
(316)262-3791 Surface Pipe: 8 5/8 inch @ 326 feet

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing Inc. License# _____

Address: _____

Company to plug at: Hour: 10:00 AM Day: 27 Month: April Year: 1994

Plugging proposal received from: Gary Lindenmuth

Company: _____ phone: _____

Were: Elevation: 2613, Anhydrite: 2024, Perfs: 4104-08, 4246-55,
8 5/8' surface csq. set @ 326' w/200 sks. 4174-78, 3982-86
4 1/2' production csq. set @ 4361' w/200 sks.
Order 300 sks. 60/40 poz 10% gel and 400 lbs. hulls.

Plugging Proposal Received by: Marvin Miller
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 3:00 PM, Day: 27, Month: April, Year: 1994

Actual plugging report: Perforated Anhydrite @ 2045 and Dakota @ 1025.
Pumped 200 sks. 60/40 poz 10% gel and 400 lbs. hulls down 4 1/2' csq.
max psi 700# shut-in psi 200#. Tied onto backside pumped 100 sks. cmt.
at 200# max psi and 100# shut-in.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: _____
MAY 02 1994

I did and not observe the plugging. Marvin Miller
Marvin L. Mifler

INVOICED
DATE MAY 03 1994
INV. NO. 40381

CONSERVATION DIVISION
Wichita, Kansas