

3-14

4-032051

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-063-20,882-00500

SE SE SW /4 SEC. 17, 15 S, 28 W
330 feet from S section line
2970 feet from E section line

Operator license# 5886

Lease Ziegenbalg well # A-1

Operator: Chief Drilling, Inc.

County Gove

Address: 120 S. Market - #300
Wichita, Kansas 67202

Well total depth 4250 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 304 feet

138.13

Aband. oil well Gas well Input well SWD D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 14 Month: March Year: 95

Plugging proposal received from: Gary Lindenmuth

Company: Chief Drilling, Inc. Phone: _____

Were: Order 250 sxs. 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION

MAR 3 1995

CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 12:00 P.M., Day: 14, Month: March, Year: 95

Actual plugging report: 8 5/8" set @ 304' w/190 sxs. cwc. 4 1/2" set @ 3980' w/150 sxs. Port collar set @ 1837' w/450 sxs. cwc. Prod. perfs. at 3806' - 3898'. Squeezed 4 1/2" w/250 sxs. cement blend w/500# hulls mixed in to Max. P.S.I. 1000#. Close in P.S.I. 1000#. Test 8 5/8" to 500# with 1/2 bbl. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO MRP
Bottom plug(in place): YES , CALC , NO Dakota plug: YES NO 1995
Plugged through TUBING , CASING . Elevation: GL

I did did not observe the plugging.

Carl Goodrow
4-032051

DATE 4-7-95
INV. NO. 42518

10.

(agent)

Form CP-2/3