

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20378-00-00
Spot: CSESWNE Sec/Twnshp/Rge: 14-15S-28W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: BENTLEY Well Number: 1A
County: GOVE Total Vertical Depth: 4310 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 205 w/150 sxs cmt
Production: Size 4.5 feet: 4295 w/225 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/17/2003 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-2311

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 400# hulls.
Fluid Level 430'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/17/2003 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

01-17-2003
Perforated casing at 1950' and 900'.
TIH with tubing to 2000'.
Mixed and pumped 100 sxs cement with 250# hulls.
Pulled up to 1000' - spotted 125 sxs cement with 150# hulls.
Pulled up to 500' - circulated cement with 50 sxs cement.
POOH. Topped with 75 sxs cement.
01-18-2003
Topped off hole with 45 sxs cement.
Hooked up to annulus and pumped 50 sxs cement.
S.I.P. 250#.

RECEIVED
JAN 23 2003
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: TBG

District: 04

Signed 

(TECHNICIAN)

T & D OIL CO. 14-15-28W
 BOX 278 #1-A BENTLEY SE SW NE
 VICTORIA, KS. 67671
 CONTR J AWBRANCO CTY GOVE
 GEOL KENNETH VEHIGE FIELD VAL HALLA
 E 2499 XB CM 7/16/78 CARD ISSUED 9/7/78 IP P 50 BOPD, N/W
 LANS 3901-06

| | | |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |

API 15-063-20,378

| LOG | TOPS | DEPTH | DATUM |
|-----------|------|-------|-------|
| ANH | | 1932 | + 567 |
| HEEB | | 3631 | -1132 |
| TOR | | 3651 | -1152 |
| LANS | | 3669 | -1170 |
| BKG | | 3983 | -1484 |
| MARM | | 4009 | -1510 |
| *FT SG | | 4169 | -1670 |
| *MLSS | | 4269 | -1770 |
| RTD | | 4310 | -1811 |
| *SMP TOPS | | | |
| | | | |
| | | | |
| | | | |

8-5/8" 205/150sx, 4 1/2" 4295/225sx
 DST (1) 3666-90/30-30-30, 780' SW,
 SIP 1054-1051#, FP 27-153#, 156-303#
 DST (2) 3746-3761/20-30-15-20, 20'
 SOCM W/FSFO, SIP 123-55#, FP 14-14#, 14-14#
 DST (3) 4016-85/30-30, 15' M W/FSO,
 ISIP 68#, NO FSIP, FP 14-14#
 DST (4) 3878-3937/15-30-15-30, 245'
 GO, 120'MGO, 590'HO&GCM, 20'W,
 SIP 1268-1241#, FP 109-342#, 369-437#
 MICT ~ PF 3901-06, FU 2700' OIL/12

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS