

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-20366-00-00  
Spot: CW2E2NE Sec/Twnshp/Rge: 14-15S-28W  
3960 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: BENTLEY Well Number: 2  
County: GOVE Total Vertical Depth: 4300 feet

Operator License No.: 101  
Op Name: KCC FEE FUND  
Address: 130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 223 w/160 sxs cmt  
Production: Size 4.5 feet: 3960 w/175 sxs cmt  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/18/2003 12:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-2311

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Fluid Level 1400'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 01/18/2003 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1880' and 850'.  
Tied onto 4 1/2" casing.  
Mixed and pumped 210 sxs cement with 400# hulls.  
S.I.P. 300#.  
Hooked up to annulus and pumped 30 sxs cement with 200# hulls.

RECEIVED  
JAN 23 2003  
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

T & D OIL CO. 14-15-28W  
 P.O. BOX 301 #2 BENTLEY APPX W/2 E/2 NE  
 VICTORIA, KS.  
 CONTR DNB DRG., INC. CTY GOVE

GEOL \_\_\_\_\_ FIELD VALHALLA CONF

E 2474 KB CM 12/7/77 CARD ISSUED 2/2/78 IF P 40 BOPD, N/W  
 LKC 3642-46

+	+	+
+	+	+

API 15-063-20,366

LOG	TOPS	DEPTH	DATUM
ANH	1908	+ 566	
HEEB	3604	-1130	
TOR	3623	-1149	
LANS	3640	-1166	
BKC	3967	-1487	
MARM	3988	-1514	
PAWN	4115	-1641	
ET SC	4150	-1676	
CHER SH	4174	-1700	
MISS	4252	-1778	
RTD	4300	-1826	

8-5/8" 223/160sx, 4 1/2" 3960/175sx  
 DST (1) 3637-70/5-60-30-60, 1565' GIP  
 1475' CGO, SIP 1065-1059#, FP 123-  
 153#, 161-459#  
 MICT - PF 3884-88, SWB 4 BWPH, BP @  
 3860, PF 3642-46, FU 2800' OIL, N/W,  
 POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS