

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-00115-00-00  
Spot: CNENE Sec/Twnshp/Rge: 14-15S-28W  
4620 feet from S Section Line, 660 feet from E Section Line  
Lease/Unit Name: BENTLEY Well Number: 1  
County: GOVE Total Vertical Depth: 4259 feet

Operator License No.: 101  
Op Name: KCC FEE FUND  
Address: 130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

Conductor Pipe: Size                    feet:  
Surface Casing: Size 8.625   feet: 118    w/100 sxs cmt  
Production: Size 5.5       feet: 4280   w/175 sxs cmt  
Liner: Size                            feet:

Well Type: OIL                            UIC Docket No:                            Date/Time to Plug: 01/17/2003 1:00 PM  
Plug Co. License No.: 6901            Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: JOE STRUBE                            Company: D S & W WELL SERVICING, INC.    Phone: (620) 587-2311

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Fluid Level 450'.

Plugging Proposal Received By: JAY PFEIFER                            WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 01/17/2003 4:00 PM                            KCC Agent: JAY PFEIFER

**Actual Plugging Report:**

Perforated casing at 1880' and 850'.  
TIH with tubing to 2000'.  
Mixed and pumped 100 sxs cement with 250# hulls.  
Pulled up to 1000' - spotted 50 sxs cement with 150# hulls.  
Pulled up to 500' - circulated cement with 110 sxs cement.  
POOH.  
Note: January 19, 2003.  
Topped off with 75 sxs cement.  
Hooked up to annulus and pumped 50 sxs cement.  
S.I.P. 200#.

RECEIVED  
JAN 23 2003  
KCC WICHITA


Remarks: COPELAND ACID AND CEMENTING.

Plugged through: TBG

District: 04

HP


Signed



(TECHNICIAN)

JAN 22 2003

10-99W MAP NO. \_\_\_\_\_ SEC. 14-15S-28W  
 STATE Kansas COUNTY Gove LOC C NE NE  
 OPER Funk-Morrison, Etal - Wichita, Kansas FT/FR \_\_\_\_\_ LINE  
 WELL #1 FARM Bentley FT/FR \_\_\_\_\_ LINE  
 POOL WC ELEV 2472 GR 2474 DF 2477 KB  
 CONT Leben Drlg tools GEOL Roger McGoy 75<sup>b</sup>  
 CO Continental Oil & Livingston Support (4450' Test)  
 INT F.R. 8-11-64 SPUD 8-28-64 COMP 10-13-64  
 TD 4366 FM Spergin PSTD



PRODUCING FR.	FROM	TO	PERF W/HOLES	TREATMENT
Lan	3726-37	32	500A	
State Pot: P 75 BOPD NW (Gr 38deg)				

WC-7 mi W of Garvey Ranch (Lan & Miss Oil)  
 8-5/8" @210' w/1.75 Sx.

*Data Inc.*

(KB Spl Tops:)					
Hb	3616	BKc	3972	FS	4158
Tor	3636	Marm	3996	Chero sh	4186
Lan	3655-1178	Paw 1m	4129	Chero sd	4239
				Sperg	4258
				RTD	4365