

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21000-00-01
Spot: NWSEW Sec/Twnshp/Rge: 3-26S-16W
5137 feet from S Section Line, 3660 feet from E Section Line
Lease Name: SOUTHWEST COLLEGE Well #: 11
County: EDWARDS Total Vertical Depth: 4435 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4390		
CIBP		4420		
PROD	5.5	4432	1308	WITH 150 SX CMT
SURF	8.625	464		WITH 325 SX CMT

Well Type: EOR UIC Docket No: E27053.1 Date/Time to Plug: 04/06/2015 10:00 AM
Plug Co. License No.: 30481 Plug Co. Name: APOLLO ENERGIES, INC.
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERGIES, INC. Phone: (620) 672-9001

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS & 2 SX CMT. PLUG AT 1040' WITH 10 SX GEL & 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/06/2015 11:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3990' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 1036' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4369	4377		
4049	4053		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: TBG

4/22/15 CKM

District: 01

Signed Steve Pfeifer
(TECHNICIAN) RECEIVED KANSAS CORPORATION COMMISSION

RECEIVED
APR 16 2015
KCC DODGE CITY

APR 20 2015
Form CP-2/3

CONSERVATION DIVISION
CC:UIC/