

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-21259-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 22-30S-6W
380 feet from S Section Line, 4950 feet from E Section Line
Lease Name: LINNEBUR A Well #: 1
County: KINGMAN Total Vertical Depth: 4485 feet

Operator License No.: 32346
Op Name: B5 OPERATING, LLC
Address: PO BOX 45
WELLINGTON, KS 67152

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4150	2100	
SURF	8.625	287		
T1	2.375	3673		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2015 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE, INC. Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/08/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3570' CAPPED WITH 5 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2100'. PULLED CASING TO 1186' SPOTTED 35 SXS CEMENT & 100 LBS OF HULLS. PULLED CASING TO 696' SPOTTED 35 SXS CEMENT & 100 LBS OF HULLS. PULLED CASING TO 341' CIRCULATED TO SURFACE WITH 130 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3633	3636		

Remarks: QUALITY WELL SERVICE SUPPLIED CEMENT FOR THIS JOB ALSO. 60/40 POZ MIX W/4% GEL. DENIED TA.

Plugged through: CSG

4/22/15 CKM

District: 02

Signed _____

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 20 2015

CONSERVATION DIVISION
WICHITA, KS