

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-129-20499-00-00  
Spot: W2SE Sec/Twnshp/Rge: 8-33S-39W  
1313 feet from S Section Line, 2005 feet from E Section Line  
Lease Name: THRASH A Well #: 1  
County: MORTON Total Vertical Depth: 6155 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5900		WITH 2 SX CMT
PROD	4.5	6154	1720	WITH 250 SX CMT
SURF	8.625	1663		WITH 800 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/01/2015 1:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 5900' WITH 2 SX CMT. PLUG AT 1700' WITH 15 SX GEL & 50 SX CMT. PLUG AT 540' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/01/2015 3:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 5900' WITH 2 SX CMT. 1ST PLUG AT 1720' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 560' WITH 50 SX CMT. 3RD PLUG AT 47' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5949	5960		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

4/22/15 CKM

District: 01

Signed \_\_\_\_\_

RECEIVED  
APR - 8 2015  
KCC DODGE CITY

Received (TECHNICIAN)  
KANSAS CORPORATION COMMISSION

APR 16 2015

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3