

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-175-20539-00-00  
Spot: NENE Sec/Twnshp/Rge: 34-33S-34W  
4567 feet from S Section Line, 681 feet from E Section Line  
Lease Name: MALIN A Well #: 1  
County: SEWARD Total Vertical Depth: 6430 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6245		WITH 2 SX CMT
PROD	4.5	6428	1742	WITH 150 SX CMT
SURF	8.625	1668		WITH 750 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/23/2015 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 6245' WITH 2 SX CMT. PLUG AT 1700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/23/2015 6:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

SET CIBP @ 6245' WITH 2 SX CMT. 1ST PLUG AT 1700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 512' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6300	6307		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

4/22/15 CKM

District: 01

Signed



Received (TECHNICIAN)  
KANSAS CORPORATION COMMISSION

APR 16 2015

CONSERVATION DIVISION  
WICHITA, KS

RECEIVED  
APR - 8 2015  
KCC DODGE CITY

