

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20608-00-01
Spot: NWSESWNE Sec/Twnshp/Rge: 27-34S-34W
2043 feet from N Section Line, 1964 feet from E Section Line
Lease Name: LENEHAN A Well #: 1
County: SEWARD Total Vertical Depth: 6615 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6494		WITH 2 SX CMT
PROD	5.5	6615	1710	WITH 140 SX CMT
SURF	8.625	1618		WITH 750 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2015 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 6494' WITH 2 SX CMT. PLUG AT 1650' WITH 10 SX GEL & 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: PARTIAL
Date/Time Plugging Completed: 03/24/2015 6:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

SET CIBP @ 6494' WITH 2 SX CMT. 1ST PLUG AT 1660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 560' WITH 40 SX CMT. 3RD PLUG AT 44' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6556	6578		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

4/22/15 CKM

District: 01

Signed 

RECEIVED
APR - 8 2015
KCC DODGE CITY



Received (TECHNICIAN)
KANSAS CORPORATION COMMISSION
APR 16 2015
CONSERVATION DIVISION
WICHITA, KS

51A