

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-21025-00-00
Spot: SW Sec/Twnshp/Rge: 22-33S-39W
1320 feet from S Section Line, 3960 feet from E Section Line
Lease Name: DEMUTH B Well #: 2H
County: STEVENS Total Vertical Depth: 6500 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6036		WITH 2 SX CMT
PROD	4.5	6499	2367	WITH 250 SX CMT
SURF	8.625	1690		WITH 800 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/31/2015 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: CIBP @ 6036' WITH 2 SX CMT. PLUG AT 1720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 03/31/2015 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 6036' WITH 2 SX CMT. 1ST PLUG AT 1731' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 540' WITH 50 SX CMT. 3RD PLUG AT 44' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6098	6116		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10YRS** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

4/22/15 CKM

District: 01

Signed

Michael J Maier

(TECHNICIAN)

RECEIVED
APR - 8 2015
KCC DODGE CITY

MA *51A*

Received
KANSAS CORPORATION COMMISSION

APR 20 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3