

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-21292-00-02
Spot: SWSWNE5W Sec/Twnshp/Rge: 29-33S-38W
1360 feet from S Section Line, 1396 feet from W Section Line
Lease Name: GREGORY E Well #: 1
County: STEVENS Total Vertical Depth: 6690 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6090		
PROD	5.5	6400	1230	WITH 250 SX CMT
SURF	8.625	1722		WITH 800 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/26/2015 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 6090' WITH 2 SX CMT. PLUG AT 1750' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2015 3:20 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 6090' WITH 2 SX CMT. 1ST PLUG AT 1760' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 560' WITH 50 SX CMT. 3RD PLUG AT 44' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6139	6176		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

4/22/15 CKM

District: 01

Signed [Signature] (TECHNICIAN)

RECEIVED
APR - 8 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
APR 16 2015
CONSERVATION DIVISION
WICHITA, KS

SA