

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-22186-00-00
Spot: NENE Sec/Twnshp/Rge: 24-33S-39W
655 feet from N Section Line, 721 feet from E Section Line
Lease Name: GREGORY D Well #: 2
County: STEVENS Total Vertical Depth: 6605 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6000		
PROD	5.5	6288	1913	WITH 145 SX CMT
SURF	8.625	1685		WITH 435 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/27/2015 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 6000' WITH 2 SX CMT. PLUG AT 1710' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/27/2015 11:30 AM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 6000' WITH 2 SX CMT. 1ST PLUG AT 1740' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 560' WITH 50 SX CMT. 3RD PLUG AT 44' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:


Top	Bot	Thru	Comments
6102	6128		
6056	6072		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

4/22/15 CKM

District: 01

Signed 

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JA

APR 16 2015

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
APR - 8 2015
KCC DODGE CITY

