

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-109-21371-00-00  
Spot: NENENW Sec/Twnshp/Rge: 1-15S-32W  
330 feet from N Section Line, 2310 feet from W Section Line  
Lease Name: KREBS Y Well #: 1  
County: LOGAN Total Vertical Depth: 4435 feet

Operator License No.: 34639  
Op Name: BLACK TEA OIL, LLC  
Address: 1014 E. 29TH ST.  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4433	1000	230 SX
SURF	8.625	265		180 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2015 10:30 AM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: COLE DINKEL Company: K & M WELL SERVICE INC. Phone: (785) 445-2441

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/300 # hulls.  
Perforations at 4230' - 4238', 4437' - 4346', 4348' - 4360'  
No Alt II Pulling casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/17/2015 2:30 PM KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Ran tubing to 4333' and pumped 65 sx cement w/150 # hulls. Pulled tubing out. Ran in log tool to find stretch on casing. Shot casing and could not pull at 2100'. Perforated at 2098' and pumped 80 sx cement down casing. Displaced 40 sx cement out perforations and left 40 sx cement in casing. Shot casing at 1000' and pumped 100 sx cement. Pulled casing up to 265' and pumped 85 sx cement full. Pulled out remaining casing. Topped of surface pipe with 20 sx cement full.

GPS: 38.78539 -100.82847

**Perfs:**

Top	Bot	Thru	Comments
4348	4360		
4337	4346		
4230	4238		

Remarks: GLOBAL CEMENT TICKET # 1585

Plugged through: TBG

District: 04

Signed  4/22/15 ckm  
(TECHNICIAN) CM

MAR 23 2015

Received  
KANSAS CORPORATION COMMISSION  
APR 16 2015  
CONSERVATION DIVISION  
WICHITA, KS