

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 3 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name J. E. Newman

Complete Address: 2005 Tower Bldg., Denver, Colorado

Lease Name Earlywine Well No. # 1

Location SE SE NE Sec. 15 Twp. 27 Rge. 15 (E) (W)

County Pratt Total Depth 4600

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Cherokee Drilling Co.

Address: 2005 Tower Bldg., Denver, Colorado License No. 350

Operation Completed: Hour 9:30AM Day 29th Month May Year 1963

The Above well was plugged as follows:

320' of 8 5/8" surface pipe, cement circulated with 300 sacks. 4552' of  
4 1/2" long string, cemented with 200 sacks. Plugged back to 4500'. Perfer-  
ated 4432' to 39'. Sanded to 4410', cemented with 3 sacks. Fluid level  
was up in hole. Plug was set at 240', 15' rock bridge, cemented through  
dump bailer with 8 sacks cement with 10% Cal-Seal, let set over night.  
Next morning hole bailed down and 12 sacks cement was added to plug.  
Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks  
to base cellar. 3517' of 4 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 6/4/63

INV. NO. 9181-W