


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. SW SW SW

LOCATION CEB-50/4

SEC. 3 TWP. 28 RGE. 12W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Rosenbawm

Operator R. W. Biss Address #320 Central Bldg. Wichita

Field _____ County Peatt

Total Depth 4612 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4 - 700ft. Circulated with cement.
5 1/2" casing set at 3555ft. Plugged back to 3800ft
with mud Lane Wells Plug & cement - Mixed
1 sack of cement at 3800ft - Shot off & pulled the
5 1/2" casing - Filled with mud to 300ft. Set Rock
Bridge & 15 sacks of cement at 300ft - Mud to
30ft - Plug & 10 sacks of cement at the surface

MAY 8 - 1950 5-8-50

STATE CORPORATION
COMMISSION

C. W. Stough
District Conservation Agent

Date 5-5-50

PLUGGING
WELL NO. 3 T 28 N 12W
BOOK PAGE 4 LINE 36