

16
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

OCT 14 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Kansas

Lease Name Thomas Well No. # 1

Location C SW NW Sec. 2 Twp. 28 Rge. 12 (E) (W) W

County Pratt Total Depth 4410

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Pickrell Drilling Co.

Address: 705 4th National Bank Bldg., Wichita, Kans. License No.

Operation Completed: Hour 12:45 PM Day 9th Month Oct. Year 1963

The Above well was plugged as follows:

280' of 13 3/8" surface pipe, cemented with 300 sacks. Hole was filled
with drilling mud to 250', 1st cementing plug, bridged with 1 sack hulls,
cemented with 40 sacks. Hole was filled with drilling mud to 40', 2nd
cementing plug, bridged with 1/2 sack hulls, cemented with 20 sacks to
base cellar. Rat hole bridges and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 10/14/63
INV. NO. 7896-W

Signed: Archie Elving
Well Plugging Supervisor