

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 17 1967

10-17-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Haskin of Davidor & Davidor has this

date requested permission to plug the following described well:

Mr. Haskin guarantees payment of the plugging fee.

Operator's full Name: Davidor & Davidor Inc.

Complete Address: 7771/4515 N. Santa E, Oklahoma City, Oklahoma.

Lease Name: Katie Lee Well No. 1

Location: NE NE Sec. 12 Twp. 33 Rge. 34 (X) (W)

County Seward Total Depth 6425' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Haskin was instructed to plug the well as follows:

8 5/8" to 1650' circulated w/ cement. 4 1/2" to 4308' cemented.

Mud 4308' to 700' Spotted 35 sacks cement 700' to 525'

Mud 525' to 50' Plug, Halls & 15 sacks cement 50' to 0'

Very truly yours,

E. Edward Johnson
Conservation Division Agent