

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Littrell of Mobil has this

date requested permission to plug the following described well:

Mr. Littrell guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corp.

Complete Address: Box 400, Hugoton, Kansas

Lease Name: Wallace Well No. 1

Location: SE SE ^{SW} Sec. 12 Twp. 33 Rge. 35 (E) (W)

County: Stevens Total Depth 2786' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Littrell was instructed to plug the well as follows:

8 5/8" to 550' circulated w/ cement. 5 1/2" to 2786' cemented.

Perforations Unknown Plug bottom w/ Sand & 50 sacks cement

Top of cement 1300' Mud 1300' to 619'

Spot 35 sacks cement 619' to 400' Mud 400' to 60'


Plug, Hulls & 15 sacks cement 60' to 0'.

INVOICED

DATE _____

INV. NO. _____

Very truly yours,


Conservation Division Agent