

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1969
CONSERVATION DIVISION
Wichita, Kansas
11-24-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bowman of Shell Oil Co. has this

date requested permission to plug the following described well:

Mr. Bowman guarantees payment of the plugging fee.

Operator's full Name: Shell Oil Company

Complete Address: 1700 Broadway, Denver, Colorado 80202

Lease Name: L.W. Sandy Well No. 1-17

Location: NE SW Sec. 17 Twp. 33 Rge. 35 (E) (W)

County Stevens Total Depth 5320' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bowman was instructed to plug the well as follows:

8 5/8" to 670' circulated w/ cement. 4 1/2" to 5240' cemented.

Top perforations 5056' Plug bottom w/ Bridg Plug set at 4900'

Mud 4900' to 600' Spotted 35 sacks cement 600' to 500'

Mud 500' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Company Pump

Very truly yours,

E. Edward Johnson
Conservation Division Agent