

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargents of Gruenerwald has this

date requested permission to plug the following described well:

Mr. Sargents guarantees payment of the plugging fee.

Operator's full Name: Gruenerwald

Complete Address: Box 909, Colorado Springs, Colorado

Lease Name: Marteny Well No. 1

Location: C SW NE Sec. 7 Twp. 33 Rge. 34 XX (E) (W)

County: Seward Total Depth 6500' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1601' circulated w/ cement. 4 1/2" to 6200' cemented.


Top perforations 4214' Plug bottom w/ 15 sacks cement.

Top of cement 4500' Mud 4500' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls ^o 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent