

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Slaby of Monsanto Co. has this

date requested permission to plug the following described well:

Mr. Slaby guarantees payment of the plugging fee.

Operator's full Name: Monsanto

Complete Address: 3545 NW 58th St. Ok., City, Ok. 73112

Lease Name: Cessna Well No. 1

Location: C NE SE Sec. 5 Twp. 30s Rge. 6 (E)(W) X

County: Kingman Total Depth 4210 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Slaby was instructed to plug the well as follows:

264' 8 5/8" casing w/ 225 sax cement. Miss. @ 4074' - Set 40

sax cement plug @ 4034' - KC. @ 3500' + - Set 40 sax cement plug

@ 3449' - Set 40 sax cement plug @ 240' - Build bridge @ 40' &

12 sax cement to top of casing. 3 sax in rat hole

Cemented by Dowell.

RECEIVED
STATE CORPORATION COMMISSION

APR 10 1979

Very truly yours,

CONSERVATION DIVISION
Wichita, Kansas


Conservation Division Agent