

State of Kansas

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 20 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Frank Pfanenstiel of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: Petroleum Inc.

Lease Name: Messenger "I" Well No. # 1

Location: C SW SW Sec. 9 Twp. 30 Rge. 6 (E) (W) W

County Kingman Total Depth 4490 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

286' of 8 5/8" surface pipe, cemented with 200 sacks. Fill hole with drilling mud to 260', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridged with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

*Archie Ebling*